

P. VENKATA REDDY

Class 1 Contractor

Brahma Tower, Plot No. 104,
N.G.o's Colony, NANDAYL. 518 502
Kurnool Dist.



Ph : 08510 - 234865
Cell : 9866863149

Camp :

Date :

CIVIL ESTIMATE


CONSTRUCTION OF AUDITORIUM AT GOVERNMENT DEGREE COLLEGE, NANDYAL

	Description	Qty	Amount
1	Earth work excavation for foundations and depositing on bank for all lifts and with an initial lead of, 10m including all operational, incidental, labour charges such as shoring ,sheeting, planking, strutting, etc. complete for finished item of work excluding seigniorage excluding dewatering charges etc .Any Soil Upto 3 m depth	155.55	62220.00
2	Back Filling with Moorum in trenches, sides of foundations and basement with initial lead in layers not exceeding 15 cm thick, consolidating each deposited layer by watering and ramming including cost and conveyance of water to work site and all operational, incidental, labour charges, hire charges of T & P etc., complete for finished item of work.	130.15	45553.20
3	Filling with Crushed stone sand in trenches, sides of foundations and basement with initial lead in layers not exceeding 15 cm thick, consolidating each deposited layer by watering and ramming including cost and conveyance of water to work site and all operational, incidental, labour charges, hire charges of T & P etc., complete for finished item of work.	366.18	219708.00
4	Plain Cement Concrete (1:5:10) proportion nominal mix (cement: fine aggregate: Coarse aggregate) using 40mm size HBG (SS5) metal from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc. to site, all operational, incidental, and labor charges such as mixing, laying and ramming concrete in layers in position not exceeding 15cm, finishing top surface, curing concrete, etc.,using concrete mixer complete for finished item of work for Foundations and Flooring Bed.	102.70	236204.94
5	Supply and placing of the Concrete 1:1.5:3 mix corresponding to IS 456 using WEIGH BATCHER / MIXER with 20mm size graded machine crushed hard granite metal (coarse aggregate) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and including all operational, incidental and labour charges such as weigh batching, machine mixing, laying concrete, curing etc.,complete but excluding cost of steel and its fabrication charges for finished item of work with minimum cement content as per IS code from standard suppliers approved by the department including pumping, centering, shuttering, laying concrete, vibrating, curing etc. complete but excluding cost of steel and its fabrication charges for finished item of work.	47.05	207038.04
6	Providing High Yield Strength Deformed (HYSD) steel bars (Fe 500 grade as per IS 1786-1985) of 8mm to 40mm diameters, cutting, bending, to required sizes and shapes placing in position with cover blocks of approved size and binding wire of 20SWG, forming grills for reinforcement work as per approved designs and drawings including cost and conveyance of bars from approved sources to site of work, including cost and conveyance of binding wire, cover blocks, chairs, overlaps spacers, dowels, wastage etc., and all operational, incidental, and labour charges such as cutting, bending, placing in position, tying etc., complete for finished item of work.	5.158584	247612.03

P. Venky

P. VENKATA REDDY**Class 1 Contractor**

Brahma Tower, Plot No. 104,
N.G.o's Colony, NANDAYL. 518 502
Kurnool Dist.



Camp :

Date :

7	Light weight Brick Masonry in C.M (1:6) prop of size 20 x 23 x 60 cms including cost and conveyance of all materials and all labour charges etc., complete for finished item of work as per S.S.	3015	422100.00
8	Plastering to brick masonry for external walls C.M (1:4) prop with 4 mm thick with dubara sponge finishing including cost and conveyance of all materials and all labour charges etc., complete for finished item of work.	723.60	130248.00
9	Supplying & fixing of Medium Teak Wood Panned Main Door of Size 4.00 Mts X 2.70 Mts made with outer frame of section 4"x5"(100x125mm) two horizontal and four verticals fixed frame, Both sides fixed with Iron grill (size:1900 x 500mm) ,(1850x500mm) made up of Vertical & Horizontal bars of 10mm Square welded to MS Flat 20x5mm around forming (100x125mm) grid and with 5mm thick pin headed glass panels (2Nos of 500mmX1900mm, 2'nos of 500mm x 500mm, 1 no of 2600mmx500mm), MT beading .The shutters should be made up of size 650mm x 1900mm (4nos) frame with 2"thick(50mm) and scantlings(planks) should be 1" (25mm thick) including fixing all fixtures such as 350mm long Brass Aldrops , 200mm Long Towetr bolts(8 nos). Brass fancy Door Handles 200mm long (2nos)out side, 150mm long (2nos) inside. Brass Hinges 150mm long (4x4=16Nos) including polishing with melamine finish including all labour charges for wrought & put up all other charges etc., complete for finished item of work.	4	54000
10	Supplying and fixing of Unplasticised Poly Vinyl Chloride (UPVC) sliding windows three track - two glass shutters sliding and one mesh shutter duly manufactured using UPVC reinforced profiles.	10	50000
11	Flooring with Vitrified polished floor tiles 600 x 600 mm of 8 to 10 mm thickness premium type 1 st quality set over base coat CM(1:8) 12 mm thick over CC bed already laid or RCC roof slab including neat cement slurry of honey like consistency spread @ 3.30 kgs per sqm jointed neatly with white cement paste to full depth mixed with pigment of matching shade, including cost of all materials like cement, sand, water and Tiles etc., complete, including seigniorage charges complete for finished item of work	874.80	481140
12	Painting to new walls with 2 coats of ready mixed Weather proof Exterior Emulsion paint of approved brand and shade over base coat of appropriate primer of approved brand making 3 coats in all to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, including cost and conveyance of all materials to work site and all operational, incidental, labour charges etc., complete for finished item of work for external walls.	723.60	75978
Total Expenditure			22,31,803.00

P. Venky



ADAMA

Adama India Pvt Ltd

Date:

Vendor Creation Form

1	Company Name	P.Venkata Reddy
2	Building Name	Auditorium Degree College
3	Additional Address	
4	Locality	Bommalasathram, Nandyala
5	Pin Code	518502
6	City	Nandyal
7	State	Andhrapradesh
8	Country	INDIA
9	FACTORY ADDRESS	
10	Telephone No	9866863149
11	Fax No	
12	Mobile No	8688100671
13	Email	pvrclass1
14	Website	
15	Contact Person	
16	Bank Name	AXIS Bank
17	Bank A/c No.	600010100023302
18	IFSC Code	UTIB0000600
19	Material Group	
20	Chapter Head	P.Venkata Reddy
21	ECC Number	
22	GSTRN No (Provide copy of provisional certificate)	37ALPPP4121M1ZM
23	GST State jurisdiction/circle	ANDHRAPRADESH
24	GST Sector/word	Contract
25	GST Commissionerate	Tirupati
26	GST Range	Tirupati
27	GST Division	KURNOOL
28	Permanent Account Number(PAN) (Provide copy of PAN card)	ALPPP4121 M
29	MSMED Applicability, Yes/ No	
	Payment Terms	

IF YES

Req Emp:

Approved By

Created By

Note:

P. Venky



Government of India
Form GST REG-06
(Sec Rule 10(1))

Registration Certificate

Registration Number :37ALPPP4121M1ZM

1.	Legal Name	VENKATAREDDY POCHA			
2.	Trade Name, if any	P VENKATA REDDY NANDYAL			
3.	Constitution of Business	Proprietorship			
4.	Address of Principal Place of Business	BRAHMATOWERS, PLOT NO 104, N.G.O S COLONY, NANDYAL POST, NANDYAL TALUKA, Kurnool, Andhra			
5.	Date of Liability	01/07/2017			
6.	Period of Validity	From	01/07/2017	To	NA
7.	Type of Registration	Regular			
8.	Particulars of Approving Authority				
Signature					
Name					
Designation					
Jurisdictional Office					
9.	Date of issue of Certificate	22/09/2017			
Note: The registration certificate is required to be prominently displayed at all places of business in the State.					

This is a system generated digitally signed Registration Certificate issued based on the deemed approval of the application for registration



GSTIN 37ALPPP412IMIZM
Legal Name VENKATAREDDY POCHA
Trade Name, if any P VENKATA REDDY NANDYAL

Details of Additional Places of Business

Total Number of Additional Places of Business in the State 0